

UNIVERSITY OF CHAKWAL
BUILDING AND WORKS DEPARTMENT

Tender for Work		Estimate for Renovation of Guest House at University of Chakwal.(City Campus)			
Total Estimated Cost Rs.		1,653,036			
Bid Amount		33,061			
Earnest Money 2 % of Estimated Amount					
Time Limit		30 Days			
Period Maintenance		As per contact agreement			
Security Released		As per contact agreement			
Tender Opening Date		22/02/2023			
MRS, 1st BI-ANNUAL-2023 (01.01.2023 to 30.06.2023) DISTRICT CHAKWAL					
ABSTRACT OF COST					
S.No	Description	Qty	Unit	Unite Rate	Amount
1	Removing cement or lime plaster	200.00	100 sft		
2	Cement plaster 1:5 upto 20' (6.00 mm) height:-b) ½" (13 mm) thick.	256.00	100 sft		
3	Distempering On Old Surface 2 coats	1406.79	100 sft		
4	Painting doors and windows, any type old surface 2 coats 1,090.90+828.45=1919.35	549.50	100 sft		
5	Painting guard bars, gates of iron bars, gratings, railing (including standards, braces etc.) and similar open work:- Old surface 2 coats (630.65+529.95=1160.60) for grills	262.80	100 sft		
6	Providing and applying weather shield of approving quality on external surface of building including preperation of surface application of primer comlete in all respects on old surface.	3593.59	100 sft		
7	Providing and fixing almirah shutter comprising of 3/4" thick both side Laminated/Glossy MDF (Karachi) sheet with 1"x3/4"deodar wood golla all around the leaf fixed on (3"x1") Kail wood frame i/c the cost of 1/2" full brass hinges, C.P.handles, catchers, screws, and rawal plugs, polishing/ paint ing 3 coat to gola & frame i/c the cost of locking arrangement complete in all respect as approved and directed by Engineer Incharge.				
	Room No-1 ,Room No-2 and Kitchen	164.47	Per sft		

8	P/F 1-1/2" thick solid flush door comprising of 2.5 mm thick Commercial ply compressed over 2.5 mm thick commercial ply over 1" thick packing wood in style and rails under proper pressure i/c the cost of nails, tower bolt , hand es, glue, sawing charges, Painting charges, sand papering and 3/8" thick matching wooden lipping as approved and directed by the Engineer Incharge.	66.45	Sft		
9	Providing and fixing false ceiling comprises of Gypsum board laminated sheet of size 2'x2'/2'x3'/ 3'x3' of specified design and thickness i/c cost of fixtures i.e galvanized angle 1" x 1" at wall sides, galvanized tee 1¼" x 1"and 1 ½" x 1" both at 4' c/c (made of Taiwan CKM or equivalent), hanging with G.I/Copper wire 16 SWG, G.I hook, Rawal Plug etc: complete in all respects as approved and directed by the Engineer Incharg i) 6 mm thic	842.27	Per sft		
10	Dismantling glazed or encaustic tiles, etc	17.50	100 Sft		
11	Cement concrete brick or stone ballast 1½ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth:-(b) Ratio 1: 4: 8	550.75	100 cft		
12	1½"(40 mm) thick mosaic flooring, consisting of ½ "(13 mm) mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :- using grey cement	991.77	100 sft		
13	Providing and laying superb quality Ceramic tiles dado of Master brand of specified size,Glossy/Matt/Texture skirting/dado of approved Color and Shade with adhesive bond over 1/2"thick (1:2) cement plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects as approved and directed by the Engineer Incharge.i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"	879.00	sft		
14	Providing and laying superb quality Ceramic tile floors of Master brand of specified size,Glossy/Matt/Texture of approved Color and Shade as per approved design with adhesive bond, over 3/4" thick (1;2) cement sand plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects and as approved and directed by the Engineer Incharge i)12"x18"/12"x24"/10"x24" /8"x24"/12"x36"	162.31	sft		

15	Providing and fitting European Coupled set of Water Closet (WC) and flushing Cistern of PORTA brand (full size) i/c the cost of CP/rubber connection, thimble, seat cover and rawal bolts complete in all respects as approved and directed by the Engineer Incharge.	3.00	Each		
16	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern), combined with foot rest (i) white	2.00	Each		
17	Providing and fixing Bathroom Accessories (7-piece set) Master brand - One Cosmetic Shelf, One Towel rod with bracket, One soap dish, One double hook, One towel ring, brush holder, toilet paper holder & looking glass i/c the cost of hardwares etc complete in all respect as approved and directed by the Engineer incharge				
	i) Plastic soap dish	4.00	Each		
	ii) Plastic toilet paper holder	4.00	Each		
	iii) Plastic tower rail	4.00	Each		
	iv) Plastic shelf 60x13 cm (24:x5") with bracket and railing	4.00	Each		
	v) Plastic Brush holder	4.00	Each		
	vi) Looking glass with plastic frame	4.00	Each		
	vii) Towel ring	4.00	Each		
18	Providing and fixing CP bath Room Set made of Sonex/Master/Faisal comprising of 3-No Tee stop cocks, lever type Basin Mixer, double Bib Cock, open wall shower, Muslim shower,waste coupling and bottle trap etc. complete in all respect as approved and directed by the Engineer incharge.(v) Muslim shower				
	(i) 3 No Tee Stop Cock (set)	3.00	Each		
	(ii) Lever Type Basin Mixer	4.00	Each		
	(iii) Double Bib Cock	4.00	Each		
	(iv) Open Type Wall Shower	4.00	Each		
	(v) Muslim shower	4.00	Each		
	(vi) Waste Coupling	4.00	Each		
19	Providing and fitting glazed earthen ware wash hand basin /vanity 56x40 cm (22"x16") including bracket set, waste pipe and waste coupling, etc.i) white, with pedestal	4.00	Each		
20	Providing and fitting "P" trap:-ii) 10 cm (4") glazed.	5.00	Each		
21	Providing and fixing Copper winded Exhaust fan with louver and shutter made of Pak/Younas/G.F.C. i/c the cost of necessary cable and hardware for connection from ceiling rose complete as approved and directed by Engineer Incharge..(a) Plastic body (ii) 10 " dia	4.00	Each		

22	Supply and erection of single core PVC insulated, PVC sheathed copper conductor, 250/440 volts grade cable (BSS-2004), in prelaid PVC pipes/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/trenches, etc. (rate for cable only):-				
i	3/0.74 mm (3/0.029")	500.00	Rft		
ii	7/0.74 mm (7/0.029")	200.00	Rft		
ii	7/0.91 mm (7/0.036")	100.00	Rft		
	Non Schedule Items				
23 N.S	Providing and fixing pvc pannelling (10"x10') or Equivalent with approve or as per drawing including fixing and arrangements etc.complete in all respect or as directed by the Engineer Incharge.	492.05	Per sft		
24 N.S	Providing and fixing false Ceiling fan 16" 2'x2' f: with remote operated 100 % pure copper wire with GFC /PAK fan or Equivalent complete in all respect or as directed by Engineer Incharge.	4.00	Each		
25 N.S	Providing and fixing Led ight 2'x2' (36 watts) in false ceiling or Equivalent complete in all respect or as directed by Engineer Incharge.(Philips) or Equivalent.	23.00	Each		
26 N.S	Supplying and erection of 56" sweep ceiling fan of (GFC,PAK,ROYAL) i/c dimmer 100 % copper winding complete in all respect or as directed by the Engineer Incharge.	3.00	Each		
	Total				
	Add 5 % PST				
	Net Total				

Amount in Words -----

Signature and Stamp of Contractor

UNIVERSITY OF CHAKWAL

BUILDING AND WORKS DEPARTMENT

Tender for Work	Renovation of Boys Hostel at University of Chakwal (City Campus)				
Total Estimated Cost Rs.	4,954,896				
Bid Amount	99,098				
Earnest Money 2 % of Estimated Amount					
Time Limit	60 Days				
Period Maintenance	As per contact agreement				
Security Released	As per contact agreement				
Tender Opening Date	22/02/2023				
MRS, 1st BI-ANNUAL-2023 (01.01 2023 to 30.06.2023) DISTRICT CHAKWAL					
ABSTRACT OF COST					
Sr.#	Description	Quantity	Unit	Unit Rate	Amount
1	Distempering On Old Surface 2 coats				
	Ground Floor	19823.01	100 sft		
	First Floor	20111.51	100 sft		
	Second Floor	14578.51	100 sft		
2	Painting doors and windows, any type old surface 2 coats 1,090.90+828.45=1919.35				
	Ground Floor	1274.00	100 sft		
	First Floor	1092.00	100 sft		
	Second Floor	847.00	100 sft		
3	Painting guard bars, gates of iron bars, gratings, railing (including standards, braces etc.) and similar open work:- Old surface 2 coats (630.65+529.95=1160.60) for grills				
	Ground Floor	486.00	100 sft		
	First Floor	504.00	100 sft		
	Second Floor	444.00	100 sft		
4	Providing and fixing wardrobe 22" (550 mm) deep consisting of RCC shelves 1½" (40 mm) thick including ½" thick vinboard boxing and back (one side ply) vinboard shutter ¾" (20 mm) thick including deodar wood lipping ¼" (6 mm) on all edges, fixes including deodar wood frame 3"x1" (75mm x 25mm) with hanger rod in centre position drawers at bottom and openable shutter on upper portion including full hinges C.P. fitting and painting 3 coats complete.				
	Ground Floor	693.00	Per sft		
	First Floor	1188.00	Per sft		
	Second Floor	693.00	Per sft		
5	b) Glazing with panes (16 oz. to 18 oz.) using deodar wooden fillets and putty.				
	for broken windows glass	120.00	Per sft		

6	Providing and fixing, expanded metal ½" to ¾" (13 mm to 20 mm) mesh 16 gauge.a) fixed to chowkat with 1" (25 mm) thick deodar wood strip and screws, etc	70.00	Per sft		
	Plumbing Items				
7	Providing and fixing CP bath Room Set made of Sonex/Master/Faisal comprising of 3-No Tee stop cocks, lever type Basin Mixer, double Bib Cock, open wall shower, Muslim shower,waste coupling and bottle trap etc. complete in all respect as approved and directed by the Engineer incharge.				
	(iii) Double Bib Cock	12.00	Each		
	(iv) Open Type Wall Shower	12.00	Each		
	(v) Muslim shower	12.00	Each		
	(vi) Waste Coupling	12.0	Each		
8	Providing and fixing, chromium plated mixing valve, for wash hand basin, sink or shower.	12.0	Each		
9	Providing and fitting plastice low down flushing cistern 13.63 litres (3 gallons) capacity, including bracket set, copper connection, etc.i) White				
	Ground Floor	4.0	Each		
	First Floor	4.0	Each		
	Second Floor	4.0	Each		
10	Providing and fitting one piece European Coupled set of Water Closet (WC) and flushing Cistern of PORTA brand (full size) i/c the cost of CP/rubber connection, thimble, normal seat cover and rawal bolts complete in all respects as approved and directed by the Engineer Incharge.				
	For bath	6.0	Each		
11	Providing and fixing looking glass 55x40 cm (22"x16") size, and 5 mm thick, first quality.	24.00	Each		
12	Providing and fixing, floor trap of cast iron, including concrete chamber all round, and C.I. grating:-ii) 10x7.5 cm (4"x3")	4.00	Each		
13	Providing, laying, cutting, jointing, testing and disinfecting G.I. pipeline in trenches, with socket joints, using G.I. pipes of B.S.S. 1387-1967 complete in all respects, with specials and valves ii) Medium Quality.a) ½" i/d (15 mm) 2.65mm thick				
	for bath	100.0	Rft		
	Electric Work				
14	Supply and erection of switches 5 Amp.ii) Piano type	75.00	Each		
15	Supply and erection of 3 pin. 5 Amp wall socket.	36.00	Each		
16	Supply and erection of 3 pin 10/15 Amp. wall socket with shoe, open type.	36.00	Each		

17	Providing and fixing Copper winded Exhaust fan with louver and shutter made of Pak/Younas/G.F.C. i/c the cost of necessary cable and hardware for connection from ceiling rose complete as approved and directed by Engineer Incharge.a) Plastic body (ii) 12 " dia	12.00	Each		
Non Schedule Items					
18 N.S	Supplying and erection of LED Bulb (18 Watt) Extra bright including Bakelite holder Local made /China (Pak Lite) sample complete in all respect or as directed by the Engineer Incharge.				
	Grround Floor	52.00	Each		
	First Floor	72.00	Each		
	Second Floor	52.00	Each		
	Total				
	Add 5% PST				
	Grand Total				

Amount in Words -----

Signature and Stamp of Contractor

UNIVERSITY OF CHAKWAL

BUILDING AND WORKS DEPARTMENT

Tender for Work	Estimate for Renovation of E-Rozgar Lab in Western Academic Block at University of Chakwal.(City Campus)				
Total Estimated Cost Rs.	578,370				
Bid Amount	11,567				
Earnest Money 2 % of Estimated Amount					
Time Limit	15 Days				
Period Maintenance	As per contact agreement				
Security Released	As per contact agreement				
Tender Opening Date	22/02/2023				
MRS, 1st BI-ANNUAL-2023 (01.01.2023 to 30.06.2023) DISTRICT CHAKWAL					
ABSTRACT OF COST					
1	Preparing surface and painting with emulsion paint:- $(1,279.15+991.55)=2270.70$	669.50	100 sft		
2	Distempering:-b) old surface 2 coat	1148.00	100 sft		
3	Painting doors and windows, any type old surface 2 coats $1,090.90+828.45=1919.35$)	157.50	100 sft		
4	Painting guard bars, gates of iron bars, gratings, railing (including standards, braces etc.) and similar open work:- Old surface 2 coats $(630.65+529.95=1160.60)$ for grills	302.40	100 sft		
5	Providing and fixing false ceiling comprises of Gypsum board laminated sheet of size 2'x2'/2'x3'/ 3'x3'of specified design and thickness i/c cost of fixtures i.e galvanized angle 1" x 1" at wall sides, galvanized tee 1½" x 1" and 1 ½" x 1" both at 4' c/c (made of Taiwan CKM or equivalent), hanging with G.I/Copper wire 16 SWG, G.I hook, Rawal Plug etc: complete in all respects as approved and directed by the Engineer Incharge.i) 6 mm thick	1350.00	Ps ² sft		
6	Supply and erection of single core PVC insulated, PVC sheathed copper conductor, 250/440 volts grade cable (BSS-2004), in prelaidd PVC pipes/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/trenches, etc. (rate for cable only):-				
i	3/0.74 mm (3/0.029")	600.00	Rft		
ii	7/0.74 mm (7/0.029")	510.00	Rft		
ii	7/0.91 mm (7/0.036")	100.00	Rft		
7N.S	Providing and fixing Led Light 2'x2' (36 watts) in false ceiling complete in all respect or as directed by Engineer Incharge.(Philips) or Equivalent	20.00	Each		

8 N.S	Providing and fixing false Ceiling fan 16" 2 x2' ft with remote operated 100 % pure copper wire with GFC /PAK fan or Equivalent complete in all respect or as directed by Engineer Incharge	10.00	Each		
9 N.S	Providing and fixing of Roller fabric Curtains (Best quality) i/c all fittings at site etc i/c labour charges complete in all respect or as directed by the Engineer Incharge.	342.00	Per sft		
	Total				
	Add 5% PST Charges				
	Net Total				

Amount in Words -----

Signature and Stamp of Contractor

UNIVERSITY OF CHAKWAL

BUILDING AND WORKS DEPARTMENT

Tender for Work	Renovtation of Engineering Academic Block at University of Chakwal (City Campus)				
Total Estimated Cost Rs.	4,981,792				
Bid Amount	99,636				
Earnest Money 2 % of Estimated Amount					
Time Limit	60 Days				
Period Maintenance	As per contact agreement				
Security Released	As per contact agreement				
Tender Opening Date	22/02/2023				
MRS, 1st BI-ANNUAL-2023 (01.01.2023 to 30.06.2023) DISTRICT CHAKWAL					
ABSTRACT OF COST					
Sr.#	DESCRIPTIONS	Quantity	Uni:	Unit Rate	Amount
1	Scraping, (b) Ordinary distamper,oil bound distamper,or paint of wall.	3284.50	100 sft		
2	Preparing surface and applying Graffiato Weather Coating (Co-polymer emulsion) of approved colour & shade with weather resistant pigment, highly water repellent with Metallic Spatula having top class finish by smoothing with a plastic Spatula, on a base coat (Primer) over well cleaned plastered surface complete in all respect as approved and directed by the Engineer Incharge.				
	Up to 20'height	18360.94	Per sft		
3	Extra labour for white washing, colour washing, priming coat and distempering, etc. from 20' (6.00 m) height and above, requiring scaffolding, for every additional 10' (3.00m) height or part thereof				
	Up to 20' to 30'height (0.407+62.05=62.46)	10314.20	Per sft		
	Up to 30' to 40'height (0.407+62.46=62.86)	9993.81	Per sft		
	Up to 40' to 50' height (0.407+62.86=63.27)	3125.40	Per sft		
4	Distempering:b) old surface:- 2 coats				
	Ground Floor	49944.84	100 Sft.		
	First Floor	56854.67	100 Sft.		
	Second Floor	36618.97	100 Sft.		
5	Painting doors and windows, any type old surface 2 coats 1,090.90+828.45=(1919.35)	393.75	100 Sft.		
6	Dismantling glazed or encaustic tiles, etc.				
	Ground Floor	1475.70	100 sft		
	First Floor	1800.70	100 sft		
	Flooring Ground/First Floor	847.72	100 sft		

7	Providing and laying superb quality Ceramic tiles dado of Master brand of specified size,Glossy/Matt/Texture skirting/dado of approved Color and Shade with adhesive bond over 1/2"thick (1:2) cement plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects as approved and directed by the Engineer Incharge.i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"				
	Ground Floor	1535.70	Per sft		
	First Floor	1800.70	Per sft		
8	Providing and laying superb quality Ceramic tile floors of Master brand of specified size,Glossy/Matt/Texture of approved Color and Shade as per approved design with adhesive bond, over 3/4" thick (1;2) cement sand plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects and as approved and directed by the Engineer Incharg. i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"				
	Flooring Ground/First Floor	847.72	Per sft		
9	P/F 1-1/2" thick solid flush door comprising of 2.5 mm thick Commercial ply compressed over 2.5 mm thick commercial ply over 1" thick packing wood in style and rails under proper pressure i/c the cost of nails, tower bolt , handles, glue, sawing charges, Painting charges, sand papering and 3/8" thick matching wooden lipping as approved and directed by the Engineer Incharge.				
	Door	313.25	per sft		
10	Providing and fixing, approved quality mortice lock.	38.00	Each		
11	Providing and fitting European Coupled set of Water Closet (WC) and flushing Cistern of PORTA brand (full size) i/c the cost of CP/rubber connection, thimble, seat cover and rawal bolts complete in all respects as approved and directed by the Engineer Incharge.	2.00	Each		
12	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern), combined with foot rest (i) white	10.00	Each		
13	Providing and fixing Bathroom Accessories (7-piece set) Master brand - One Cosmetic Shelf, One Towel rod with bracket, One soap dish, One double hook, One towel ring, brush holder, toilet paper holder & looking glass i/c the cost of hardwares etc complete in all respect as approved and directed by the Engineer incharge				
	i) Plastic soap dish	10.00	Each		
	ii) Plastic toilet paper holder	10.00	Each		
	iii) Plastic tower rail	10.00	Each		
	iv) Plastic shelf 60x13 cm (24:x5") with bracket and railing	10.00	Each		
	v) Plastic Brush holder	10.00	Each		
	vi) Looking glass with plastic frame	10.00	Each		
	vii) Towel ring	10.00	Each		

14	Providing and fixing CP bath Room Set made of Sonex/Master/Faisal comprising of 3-No Tee stop cocks, lever type Basin Mixer, double Bib Cock, open wall shower, Muslim shower,waste coupling and bottle trap etc. complete in all respect as approved and directed by the Engineer incharge.(v) Muslim shower				
	(i) 3 No Tee Stop Cock (set)	30.00	Each		
	(ii) Lever Type Basin Mixer	10.00	Each		
	(iii) Double Bib Cock	10.00	Each		
	(v) Muslim shower	10.00	Each		
	(vi) Waste Coupling	10.00	Each		
15	Providing and fitting glazed earthen ware wash hand basin /vanity 56x40 cm (22"x16") including bracket set, waste pipe and waste coupling, etc.i) white, with pedestal	6.00	Each		
16	Providing and fitting "P" trap:-ii) 10 cm (4") glazed.	10.00	Each		
17	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):(f) Ratio 1: 2: 4	96.62	100 cft		
	Total				
	Add 5% PST Charges				
	Net Total				

Amount in Words -----

Signature and Stamp of Contractor

UNIVERSITY OF CHAKWAL
BUILDING AND WORKS DEPARTMENT

Tender for Work		Estimate for Renovation of Faculty Hostel at University of Chakwal			
Total Estimated Cost Rs.		2,501,796			
Bid Amount					
Earnest Money 2 % of Estimated Amount		50,036			
Time Limit		60 Days			
Period Maintenance		As per contact agreement			
Security Released		As per contact agreement			
Tender Opening Date		22/02/2023			
MRS, 1st BI-ANNUAL-2023 (01.01.2023 to 30.06.2023) DISTRICT CHAKWAL					
ABSTRACT OF COST					
	First Floor	7257.58	100 sft		
2	Painting doors and windows, any type old surface 2 coats 1,090.90+828.45=1919.35				
	Ground Floor	651.00	100 sft		
	First Floor	672.00	100 sft		
3	1½"(40 mm) thick mosaic flooring, consisting of ½ "(13 mm) mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :- using grey cement	2345.97	100 sft		
4	Dismantling glazed or encaustic tiles, etc.				
	For faculty Bath	730.00	100 sft		
5	Providing and laying superb quality Ceramic tiles dado of Master brand of specified size, Glossy/Matt/Texture skirting/dado of approved Color and Shade with adhesive bond over 1/2" thick (1:2) cement plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects as approved and directed by the Engineer Incharge. i) 12"x18"/12"x24"/10"x24"/8"x24"/12"x36"				

	faculty bath	681.25	Per sft		
6	Providing and laying superb quality Ceramic tile floors of Master brand of specified size,Glossy/Matt/Texture of approved Color and Shade as per approved design with adhesive bond, over 3/4" thick (1;2) cement sand plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects and as approved and directed by the Engineer Incharg. i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"				
	faculty bath floor	189.00	Per sft		
	Plumbing Items				
7	Providing and fitting glazed earthen ware wash				
	Ground Floor	6.00	Each		
	First Floor	8.00	Each		
8	Providing and fitting plastice low down flushing cistern 13.63 litres (3 gallons) capacity, including bracket set, copper connection, etc.i) White				
	Ground Floor	6.00	Each		
	First Floor	8.00	Each		
9	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern), combined with foot rest. i) white				
	Ground Floor	2.00	Each		
	First Floor	4.00	Each		
10	Providing and fixing CP bath Room Set made of Sonex/Master/Faisal comprising of 3-No Tee stop cocks, lever type Basin Mixer, double Bib Cock, open wall shower, Muslim shower,waste coupling and bottle trap etc. complete in all respect as approved and directed by the Engineer incharge.(v) Muslim shower				
	(i) 3 No Tee Stop Cock (set)	14.00	Each		
	(ii) Lever Type Basin Mixer	14.00	Each		
	(iii) Double Bib Cock	14.00	Each		
	(iv) Open Type Wall Shower	14.00	Each		
	(v) Muslim shower	14.00	Each		
	(vi) Waste Coupling	14.00	Each		

11	Providing and fixing Bathroom Accessories (7-piece set) Master brand - One Cosmetic Shelf, One Towel rod with bracket, One soap dish, One double hook, One towel ring, brush holder, toilet paper holder & looking glass i/c the cost of hardwares etc complete in all respect as approved and directed by the Engineer incharge				
	i) Plastic soap dish	14.00	Each		
	ii) Plastic toilet paper holder	14.00	Each		
	iii) Plastic tower rail	14.00	Each		
	iv) Plastic shelf 60x13 cm (24:x5") with bracket and	14.00	Each		
	v) Plastic Brush holder	14.00	Each		
	vi) Looking glass with plastic frame	14.00	Each		
	vii) Towel ring	14.00	Each		
12	Providing, laying, cutting, jointing, testing and disinfecting G.I. pipeline in trenches, with socket joints, using G.I. pipes of B.S.S. 1387-1967 complete in all respects, with specials and valves.i) Light Quality b) ¾" i/d (20 mm) 2.35mm thick	180.00	Per rft		
12.1	a) ½" i/d (15 mm) 2mm thick	200.00	Per rft		
13	Providing, laying, testing and commissioning µ-PVC (Un plasticized Polyvinyl Chloride) Schedule pipe of nominal diameter, Dadex/Popular / Beta or equivalent, i/c the cost of solvent and specials complete as approved and directed by the Engineer Incharge.a) Schedule 40 (viii) 4"	100.00	Per rft		
	Electric Work				
14	Supply and erection of single core PVC insulated, PVC sheathed copper conductor, 250/440 volts grade cable (BSS-2004), in prelaid PVC pipes/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/trenches, etc. (rate for cable only):-				
i	3/0.74 mm (3/0.029")	200.00	Per Rft		
ii	7/0.74 mm (7/0.029")	100.00	Per Rft		
iii	7/0.91 mm (7/0.036")	150.00	Per Rft		
15	Supply and erection of M.S. sheet box of 16 SWG, 10 cm (4")deep, with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators, switches, plugs, etc				

i	17.5 x 10 cm (7"x4")	6.00	Each		
ii	10 x 10 cm (4"x4")	6.00	Each		
ii	22.5 x 10 cm (10"x12")	6.00	Each		
16	Supply and erection of switches 5 Amp.ii) Piano type	74.00	Each		
17	Supply and erection of 3 pin. 5 Amp wall socket.	24.00	Each		
18	Supply and erection of 3 pin 10/15 Amp. wall socket with shoe, open type.	12.00	Each		
19	Supply and erection of 3 pin switch and plug combined, ditto recessed type				
i	5 Amp	12.00	Each		
ii	10/15 Amp	12.00	Each		
20	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete.ii) single rod (40 watts) with one choke and one starter.	28.00	Each		
21	Providing and fixing Copper winded Exhaust fan with louver and shutter made of Pak/Younas/G.F.C. i/c the cost of necessary cable and hardware for connection from ceiling rose complete as approved and directed by Engineer Incharge..(a) Plastic body (ii) 10 " dia				
	Ground Floor	6.00	Each		
	Fist Floor	8.00	Each		
	Non Schedule Items				
22 N.S	Supplying and erection of LED Bulb (18 Watt) Extra bright including Bakelite holder Local made / China (Pak Lite) sample complete in all respect or as directed by the Engineer Incharge.				
	Grround Floor	20.00	Each		
	First Floor	20.00	Each		
23 N.S	Providing and fixing of Wooden Wardrobe 24" Deep making with MDF Sheet 3/4" thick, lamination Sheet 3/4" thick ,wooden strip 2"x 3/4" (kaeil) Full size, Pvc gola 3/4", Steel nail 2",Screw 3/4",Screw 5/8", Hinges 3/4" X 6',magnatic ketcher (big),Handle 6" (fancy),Steel Pipe 1" Dia ,Side Braket,Nails,Nails, No 16 (2"),Glue and painting/polishing i/c labour charges. complete in all respect or as directed by the Engineer Incharge.				

	Ground Floor	252.00	Per sft		
	First Floor	336.00	Per sft		
	Total				
	Add 5% PST				
	Grand Total				

Amount in Words -----

Signature and Stamp of Contractor

UNIVERSITY OF CHAKWAL

BUILDING AND WORKS DEPARTMENT

Tender for Work	Weather Shield of Boundary wall Engineering side at University of Chakwal (City Campus)				
Total Estimated Cost Rs.	312,365				
Bid Amount					
Earnest Money 2 % of Estimated Amount	6,247				
Time Limit	15 Days				
Period Maintenance	As per contact agreement				
Security Released	As per contact agreement				
Tender Opening Date	22/02/2023				
MRS, 1st BI-ANNUAL-2023 (01.01.2023 to 30.06.2023) DISTRICT CHAKWAL					
ABSTRACT OF COST					
Sr.#	DESCRIPTIONS	Quantity	Unit	Unit Rate	Amount
1	Removing cement or lime plaster	139.50	100 sft	462.00	644.49
2	Cement plaster 1:5 upto 20' (6.00 mm) height:-b) ¼" (13 mm) thick.	139.50	100 sft	3,313.45	4622.26
3	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect b) old surface:				
	Old surface 2 coats	13903.50	100 sft	2101.80	292223.76
	Total				
	Add 5 % PST				
	Net Total				

Amount in Words -----

Signature and Stamp of Contractor